



**NOTES**

- (1) Plug all empty ducts
- (2) Mark all circuit to show location of the other terminal.
- (3) Working clearance is 4' in front of the doors and 1' from the sides.

**REFERENCES**

- (1) See DS-18-26.0 Overhead and Underground Torque Values

**Material List**

Item	Quan.	Description	Stock #
A	1	Secondary Pedestal	5985-000016
B	1	Multiple Secondary Connector	5935-233311
C	1	2294 Padlock	5340-187771
D	1	4' Don't Fence Me In Decal	0100-004436

**Secondary Pedestal**